## MYSORE CITY MUNICIPALITY.

*Dated 20th February* 1918.

Notice is hereby given that sealed tenders will be received at the office of the President, City Municipal Council, up to 31st March 1918 for extending Devaraj Market Block B. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1918.

2. The plans, detailed estimate and conditions may be seen at the Municipal Engineer's office at Town Hall, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending Block B of Devaraj Market" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Municipal Council, Mysore, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be pasted on the notice board, in the Municipal Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

An approximate estimate of quantities required for constructing the block B of Devaraj Market Extension.

| Details of work | Per | Quantity |
|---|---|---|
| Earthwork excavating foundation and filling in basement | C. yd. | 402 |
| Concrete filling in foundation | C. ft. | 4,311 |
| Burnt brick in mortar foundation and basement | " | 6,336 |
| Do superstructure | " | 12,875 |
| Burnt brick in mortar plain arch work | " | 53 |
| Cut stone bases of pillars nicely dressed | No. | 15 |
| Burnt stone slabs dressed 6" thick | S. ft. | 1,881 |
| Teakwood panelled doors with hinges, locks, bolts, etc. | " | 1,728 |
| Do glazed ventilators rectangular, complete | " | 288 |
| Do work wrought and put up big scantlings | C. ft. | 368·55 |
| Do do small scantlings | " | 665·16 |
| Roofing with pukka terrace 9" thick complete | Sqr. | 59·44 |
| Plastering with chunam | " | 208·6 |
| White and colourwashing | " | 208·6 |
| Flooring with Cuddappah slabs over 3" concrete and cement pointing | " | 45·43 |
| Silicate painting | " | 40·32 |
| Cornice 9" thick ornamental | R. ft. | 419 |
| Do 4½" thick for parapet | " | 299 |
| Ornamental parapet wall 2' high | " | 150 |
| Do teakwood cave board 10" wide and 1" thick | " | 150 |
| Do work for pedastals | No. | 16 |
| Masonry finials, large | " | 16 |
| Do small | " | 20 |

J. V. KARVE,
*Senior Vice-President.*

## MYSORE STATE RAILWAYS.

*Notice dated 21st February* 1918.

AUCTION SALE.

Thirteen casuarina poles lying unclaimed at Kolar will be sold by public auction at Kolar station on Thursday the 4th April, 1918, at 12 noon, unless the owner takes delivery of the same before the 20th of March after paying the wharfage charges due thereon.

B. VENCOBA RAO,
*Traffic Manager.*

## PRIVATE ADVERTISEMENTS.

IN THE COURT OF THE DISTRICT JUDGE, BANGALORE DIVISION.

*Miscellaneous Case No.* 52 *of* 1917-18.

Siddappa, son of Veerasetti Anniappa, Chikballapur ... *Applicant.*

Whereas an application under the Probate and Administration Regulation, for grant of Probate of the Will of Nanjundappa, son of V. Channavirappa, late of Nagarathpet, Bangalore City, has been made by the applicant and whereas the 22nd March 1918, has been fixed